

TOWN OF NEWBURGH PLANNING BOARD TECHNICAL REVIEW COMMENTS

PROJECT NAME: GARDNER RIDGE

PROJECT NO.: 2-29

PROJECT LOCATION: GARDNERTOWN ROAD NEAR GIDNEY AVENUE

SECTION 75, BLOCK 1, LOT 4.12

REVIEW DATE: 27 OCTOBER 2023
MEETING DATE: 2 NOVEMBER 2023
PROJECT REPRESENTATIVE: DARREN DOCE, P.E.

- 1. Town Board and Highway Superintendents approval for the re-alignment of Creek Run Road must be received.
- 2. The project was re-circulated for Lead Agency on 5 October 2023. The thirty day time frame for response from outside agencies has not lapsed as of the date of this meeting.
- 3. The applicant's representative are requested to confirm the amount of export material from the site. The Long Form EAF submitted does not identify any volume of material to be removed from the site.
- 4. The plans identify an area of potential blasting at 1.6 acres. When evaluating the environmental impact's the potential impacts for blasting should also be evaluated.
- 5. The applicants are requested to confirm the status of the Outside User Sewer Agreements.
- 6. Health Department approval for watermain extension with hydrants is required.
- 7. Hydrant locations should be evaluated by Code Enforcement and Jurisdictional Emergency Services. Additional hydrant should be evaluated at the Senior Complex as a hydrant must be located within the specified code distance from the Fire Department OSY connection.
- 8. Hydrant locations in the vicinity of Buildings #4 & 5 should be further reviewed.
- 9. The proposed water system creates a long dead end watermain servicing the site. Water is proposed to be brought in from Creek Run Road up the site access drive terminating in front of Building #3. The applicants representative are requested to evaluate whether an internal loop within the site or continuation of the watermain out the fire access road should be considered.
- 10. Hydrant placement along the access drive should be evaluated.

Gardner Ridge (2-29) 2 November 2023

11. Legal documents must be provided to the Town for review regarding compliance with all sections of the Senior Housing Code Section 5-48.

- 12. Confirmation that the City of Newburgh Flow Acceptance letter has been issued for the project should be received.
- 13. The revised plans were referred to the Orange County Planning Department of 5 September 2023.
- 14. The applicants have submitted a Tree Survey Map. The Survey Map was completed utilizing sample plots. The location of the 5 half acre sample plots was reviewed and approved by this office on 18 August 2023. The applicants have had the Tree Survey and Analysis performed by Hudson Forestry Services, LLC.
- 15. Cost Estimates for stormwater management, landscaping, tree preservation are required for determination of required securities. Estimate for water and sewer improvements are to be submitted upon application for those permits.

Respectfully submitted,

MHE Engineering, D.P.C.

atres of Denes

Patrick J. Hines Principal

PJH/kbw

Thomas B. Olley, P.E., P.L.L.C.

Engineering & Land Planning 152 Orange Avenue • Walden, NY 12586 (845) 778-5638 • Fax (845) 778-1137

October 20, 2023

Mr. John Ewasutyn, Chairman Town of Newburgh Planning Board 308 Gardnertown Road Newburgh, NY 12550

Re: Gardner Ridge

Gardnertown Road Section 75, Block 1, Lot 4.12

Dear Mr. Ewasutyn:

We are submitting twelve (12) copies of the revised Amended Site Plan sheets on behalf of Gardner Ridge Associates.

The plans address the most recent consultant and Planning Board Comments.

A Brief response to the consultants' most recent comments are provided below. Collier Engineering will address the Traffic Consultant comments related to their plans under separate cover.

MHE Engineering Comment Memo July 28, 2023

- 1. A Tree Survey has been conducted in accordance with the Town's Tree Preservation Code. The results of the tree survey and the required calculations are shown on a newly added Sheet 16 of the Site Plan Set.
- 2. Highway Supervisor comments have been addressed in separate correspondence from Collier's Engineering.
- 3. The Project has been resubmitted for County Planning review.
- 4. The Project has been re-circulated under SEQRA.
- 5. Health Department Approval will be renewed following the Board's SEQRA determination.
- 6. All work has been relocated outside of the 100 Year flood Boundary.
- 7. Access gates have been shown on the site plan for both the emergency and maintenance access drives. The location of the gates along Gardnertown Road are situated to allow emergency or maintenance vehicles to pull in and not block Gardnertown Road.

- 8. The Water and Sewer notes (found on the detail sheets) have been updated.
- 9. A stormwater Facilities Maintenance Agreement will be executed prior to Final Approval.
- 10. All Drainage and Water Main Crossings of the Sanitary Sewer Main have been added to the Profile Sheets.
- 11. The labels for the Sanitary sewer pipe between manholes 10 and 12 have been corrected.
- 12. Missing Pipes and labels have been corrected for the storm drainage bioretention systems.
- 13. Outlet Structure 1 has been clarified on the plans.
- 14. An emergency spillway has been added to the extended detention basin.
- 15. All Drainage and Water Main Crossings of the Sanitary Sewer Main have been added to the Profile Sheets.
- 16. The details of CB-3 have been updated.
- 17. Fencing has been shown around the plunge pools. These are the only permanent water features.
- 18. Access gates have been added to the maintenance roads.
- 19. The wetland outlet pipe has been labeled.
- 20. The design of the bioretention area to the north of the Senior Apartments has been updated.
- 21. The sewer line to the rear of Buildings 1 and 2 has been fully labeled.
- 22. The rip-rap steepened slope has been redesigned as a vegetated steepened slope.

Creighton Manning Engineering Comment Memo August 1, 2023

- 1. The emergency access gate near Gardnertown Road has been positioned to provide for an emergency vehicle to be pulled completely off the public roadway.
- 2. The maintenance road will have a similar gate. It also has been positioned to allow maintenance vehicles and equipment to fully clear Gardnertown Road.
- 3. The suggested super-elevation has been incorporated into the design of the intersection of the main Road and the west Rowad at Station 12+36.
- 4. The intersections of West Road have been indicated on the profiles.

Comments 5 through 11 are address by Collier's Engineering under separate cover.

We believe that all of the Consultant's comments have been fully addressed in the submission.

Please feel free to contact me should you have any questions regarding this matter.

∀ery truly yours,

Thomas B. Olley, P.

cc: Kenneth Wersted

Dominic Cordisco Patrick Hines

Joseph Millstein

Vince Doce

400 Columbus Avenue Suite 180E Valhalla New York 10595 Main: 877 627 3772 colliersengineering.com



October 19, 2023

Chairman John Ewasutyn Town of Newburgh Planning Board 21 Hudson Valley Professional Plaza Newburgh, NY 12550

Gardner Ridge
Town of Newburgh, Orange County, New York
Colliers Engineering & Design Project No. 14000375B

Dear Chairman Ewasutyn and Members of the Planning Board:

The following items are in response to comments contained in the Creighton Manning (CME) letter dated August 1, 2023 as well as those discussed with the Planning Board at the August 3, 2023 meeting.

Proposed Site Plan Amendment

1. The revised site plan adds an emergency access point approximately 440 feet west (uphill) of the main entrance. The access is proposed to be grass pavers similar to that used across the street at Gardnertown Commons (Farrell). A detail of the emergency gate is provided, and it is noted in the letter to the planning board that there will be a gate installed at both ends of the emergency access, but they are not depicted on the plans. We suggest the gate near Gardnertown Road be located far enough off the road to allow an emergency vehicle to pull off the road before stopping and opening the gate.

Response: The gates and detail for such are now indicated on the site plans. The gate on the Gardnertown Road side is positioned to allow a fire truck to pull in off the road when opening the gate.

2. A stormwater basin access road is proposed about 60 feet east (downhill) of the main entrance. This will be a stabilized but grassed access "road". Will this be gated as well? If so, the gate should allow room for a service vehicle to pull off the road to open the gate.

Response: A gate will be installed as noted at this location.

3. The junction of the Entrance Road intersects the West Road at station 12+50(+/-) where the grades transition from a +10% to a +1% grade. West Road enters on a -10% grade. Consider super elevating the road to be reverse crown, banked 2% to the left so it is an easier transition from West Road to Entrance Road.

Response: The site plan has been revised to reflect the superelevation for that portion of the road.



4. Add callout to Entrance Road profile showing location of intersection with West Road.

Response: The callout has been added to the site plan.

Conceptual Improvement Plan

5. Plans show guide rail on both sides of realigned Creek Run Road, specify type of guide rail and end assembly types.

Response: A box beam guiderail (Item No. 606.10) similar to that which currently exists on Gardnertown Road west of the site, is now specified along both sides of the realigned Creek Run Road.

6. Stone apron detail lists incorrect item for light stone fill and shows a 4' length of stone apron but stone apron lengths vary based on pipe size and velocity of storm flow. Also, detail lists geotextile bedding under light stone fill but this is no longer an approved method, a stone bedding material shall be installed, detail should be updated.

Response: The item number for the stone fill has been corrected. Please note the detail provided is a generic detail for a stone lined apron and further detail will be provided for each outlet location upon completion of the final drainage design.

7. A detour plan is provided for when Creek Run Road is closed to be reconstructed between Stony Run Road and Gardnertown Road. What is the approximate duration of closure?

Response: Most of the work for the realigned Creek Run Road can be advanced while maintaining the existing roadway operation. The final work connecting the new portion of roadway to the remaining existing portion of Creek Run Road is expected to require a closure for less than a week to complete and open it again to traffic.

8. Taft Ave is the primary route for eastbound and westbound traffic on Creek Run Road. Road names should be labeled on the plan.

Response: Road names have been added to the detour plan.

9. Consider a "Road Closed ½ Mile Ahead, Local Traffic Only" or a "Road Closed to Thru Traffic" sign at Creek Run Road and Taft Ave. Consider a "Detour [Straight Arrow]" sign on the Taft Ave NB approach to Creek Run. Consider a second "Road Closed" sign on Creek Run Rd at Stony Run Rd to deter drivers from reaching the actual hard closure and turning around in the driveway of house #42 and #44. The six houses beyond this intersection can drive around it.

Response: The recommended signing additions have been added to the revised plans.



10. The westbound detour carries traffic up Gardnertown Road, south on Taft Ave, then into the neighborhood on N. Dix Avenue then Hill Run Road. Consider simplifying the detour by carrying traffic south on Taft and ending the detour at Creek Run Road. Residents in the neighborhood can find their way back to their street, but through traffic shouldn't be carried into the neighborhood.

Response: Comment noted. The detour plan has been revised accordingly to reflect this suggested change.

11. The above comments (see attached plan comments) should be considered in consultation with the Town's Highway Supervisor. Ultimately his direction should be followed.

Response: The revised plans have been forwarded to the Town Highway Supervisor and we will continue to coordinate with him, and the work will be implemented as per his direction.

In addition, responses to the verbal comment from the Planning Board are attached to this letter.

Sincerely,

Colliers Engineering & Design, Architecture, Landscape Architecture, Surveying, CT P.C.

Philip Grealy, Ph.D., P.E.

Geographic Discipline Leader

R:\Projects\2014\14000375B\Correspondence\OUT\231019PJG_CM 8.1.23 R2C.docx



Project No. 14000375B October 19, 2023

At the August 3, 2023 Planning Board meeting, the details of the proposed access improvement plans were presented, and several verbal comments were received from the Planning Board Members as follows:

• Frank Gallo – Will the work require a closure of Gardnertown Road? How long will the duration be?

Response: Gardnertown Road will remain open during the construction and use of flagmen and other traffic control measures will be used. The road closure would only involve the last portion of the connection of the new Creek Run Road to the remaining portion of Creek Run Road and closure of the old roadbed. The traffic diversion plans have been developed and Taft Avenue would be used for vehicles to and from the neighborhoods along Creek Run Road and for any other through traffic. All comments received from CME have been incorporated into the plans. The other construction work related with the new portion of Creek Run Road can be completed while the remaining Creek Run Road stays open.

• David Dominic – Had questions regarding the sight distances and how much they would be improved.

Response: The clearing of vegetation and widening improvements would significantly improve sight distance and coming down the hill vehicles will be able to see all the way to the area of the bridge culvert on the approach to the intersection with Gidney Avenue. This is more than double that which is available under current conditions.

• Stephanie Delucca – Comments regarding the traffic control, queuing, and the alignment of the new Creek Run Road.

Response: The alignment of Gardnertown Road would remain as. The widening that will provide the left turn lanes, pavement resurfacing, and sight distance improvements are those items that will be completed by the Applicant. The site driveway approach and the Creek Run Road approach would be stop-sign controlled at their intersection with Gardnertown Road and Gardnertown Road traffic would remain having the right-of-way.

Questions regarding the queuing at Gidney Avenue.

Response: The queue lengths would be improved by the widening and there would be a separate left turn lane for vehicles turning into the site as well as for those turning onto Creek Run Road, which would improve the overall traffic operations and flow.



• Ken Mennerich – Recommended that instead of the riprap that a vegetative alternative be explored.

Response: The rip rap has been removed from the plans. We will finalize the treatment in this area with the Highway Superintendent to ensure that nothing significant will grow in that area to block sight distance.

- John Ward No further comments.
- Cliff Browne No further comments.
- John Ewasutyn Suggested that salt tolerant plantings be used along the roadway.

Response: The drainage is being improved to capture runoff and we will ensure that salt tolerant plantings are used. This will be coordinated with the Town Highway Superintendent and other Town consultants.

R:\Projects\2014\14000375B\Correspondence\OUT\231019PJG_8.3.23 Meeting Notes.docx

SITE PLAN GARDNER RIDGE APARTMENTS

GARDNERTOWN ROAD

TOWN OF NEWBURGH, ORANGE COUNTY, NY

JANUARY 28, 2016 REVISED OCTOBER 20, 2023

DENSITY CALCULATIONS:

TOTAL PARCEL AREA = 23.4<u>+</u> AC. LESS WETLANDS, EASEMENTS/R.O.W.s, 100-YR FLOODPLAINS AND SLOPES 25% OR GREATER = 7.4<u>+</u> AC. 16.0<u>+</u> AC. MULTIPLE FAMILY DWELLINGS MAXIMUM ALLOWABLE DENSITY= 6 DU/ACRE ALLOWABLE NUMBER OF UNITS= 96 DWELLING UNITS

DENSITY BONUS FOR PROJECTS CONSISTING OF SENIOR CITIZEN MULTIPLE DWELLING UNITS AND NON-SENIOR- CITIZEN MULTIPLE DWELLING UNITS: MAXIMUM ALLOWABLE UNITS 144 UNITS

BONUS UNITS PROPOSED = 144 UNITS - 96 UNITS = 48 UNITS SENIOR HOUSING UNITS REQUIRED = 48 BONUS UNITS/3 = 16 UNITS NON-SENIOR APARTMENTS PROPOSED = 108 UNITS SENIOR HOUSING PROPOSED = 36 UNITS

SENIOR HOUSING UNITS REQUIRED = 48 UNITS/3 = 16 UNITS

BONUS UNITS = 144 UNITS - 96 UNITS = 48 UNITS

PARKING CALCULATIONS:

SPACES REQUIRED (2 SPACES/DU REQ.)= 216 SPACES GARAGES = 60 SPACES PARKING LOT SPACES = 101 SPACES NON-SENIOR APARTMENTS: SPACES PROPOSED = 221 SPACES SPACES REQUIRED (2 SPACES/DU REQ.)= 72 SPACES SPACES PROVIDED: PARKING LOT SPACES = 72 SPACES SPACES PROVIDED = 9 SPACES

TOTAL PARKING PROVIDED: 307 SPACES ACCESSIBLE PARKING SPACES (NYS BUILDING CODE SECTION 1106): SPACES REQUIRED 301 -400 SPACES = SPACES PROVIDED: 16 SPACES PROVISIONS SHALL BE PLACED IN EACH LEASE AGREEMENT THAT REQUIRES EACH TENANT WITH A GARAGE TO MAINTAIN THAT GARAGE FOR THE PURPOSE OF PARKING

SHEET INDEX

SHEET NO.	DESCRIPTION			
cs	COVER SHEET			
1	EXISTING CONDITIONS			
2	OVERALL SITE PLAN			
3	LAYOUT & DIMENSION PLAN			
4	GRADING PLAN			
5	ROCK REMOVAL PLAN			
6	UTILITY PLAN			
7	EROSION & SEDIMENT CONTROL PLAN			
8	ROAD PROFILES			
9	ROAD PROFILES			
10	SANITARY SEWER PROFILES			
11	SITE DETAILS			
12	WATER DETAILS			
13	SEWER DETAILS			
14	DRAINAGE DETAILS			
15	EROSION CONTROL DETAILS			
16	TREE SURVEY			

RECORD OWNER

GARDNER RIDGE ASSOCIATES 134 FAIRVIEW ROAD ROCKAWAY, NJ 07866


CONSULTING ENGINEER

THOMAS B. OLLEY, PE, PLLC 152 ORANGE AVENUE WALDEN, NY 12586 CONTACT: THOMAS B. OLLEY, PE (845) 778-5638

SURVEYOR:

MARTIN F. ANTHONISEN JR., PLS 1422 LONG MEADOW ROAD, TUXEDO, NY

- 1. SENIOR CITIZEN UNITS ARE LIMITED TO 1000 S.F. MAAXIMUM IN ACCORDANCE WITH TOWN OF NEWBURGH ZONING CODE SECTION 185-48 (4).
- 2. SENIOR CITIZEN UNITS SHALL BE DESIGNED AND CONSTRUCTED FOR THE NEEDS OF SENIORS AND IS SUBJECT TO THE MANAGEMENT OR OTHER LEGAL RESTRICTIONS THAT REQUIRE ALL UNITS DESIGNATED AS SENIOR CITIZEN HOUSING UNITS TO BE OCCUPIED BY PERSONS 55 YEARS OF AGE OR OLDER. NOTWITHSTANDING THE FOREGOING, ADULTS UNDER 55 YEARS OF AGE AND CHILDREN MAY RESIDE IN THE UNITS WHERE:
- 2.1. THE ADULT IS THE SPOUSE OF A PERSON 55 YEARS OF AGE OR
- 2.2. THE ADULT'S PRESENCE IS ESSENTIAL FOR THE PHYSICAL CARE OF A PERSON 55 YEARS OF AGE OR OLDER;
- 2.3. THE MINOR CHILDREN ARE RESIDING WITH THEIR PARENT, PARENTS OR LEGAL GUARDIANS WHERE THEIR PARENT, PARENTS OR LEGAL GUARDIANS ARE 55 YEARS OF AGE OR OLDER, AND THE MINOR CHILDREN RESIDING THEREIN ARE UNDER A PHYSICAL OR OTHER DISABILITY AND CANNOT CARE FOR THEMSELVES.





V 0 0 4 E 2 L





AR RD


DATE: JANUARY 28, 2016





























11 OF 16 DATE: JANUARY 28, 2016

GATE VALVE DETAIL


NOT TO SCALE

NON-RISING STEM RESILIENT WEDGE GATE VALVE, OPERATING DIRECTION AND MODEL TO CONFORM WITH WATER DEPARTMENT STANDARDS.

OR EYEBOLTS. (2)3/4" GALVANIZED STEEL RODS WITH MALIABLE IRON

2. IF VALVE IS TO BE RODDED, PROVIDE VALVE WITH RODDING FLANGES

NUTS AT 180°SPÀCING SHALL BE USED FOR RODDING VALVES.




—SURFACE TREATMENT PER PLAN & DETAILS. COMPACTED RUN OF TRENCH BACKFILL IN EASEMENT AREAS AND R.O.B. GRAVEL UNDER PAVED AREAS, IF EXCAVATED MATERIAL IS UNSUITABLE A.O.B.E. VARIES MŅN. - COMPACTED BEDDING MATERIAL FOR TRENCH BOTTOM, GRADATIONAL ANALYSIS. 6"+50% O.D. WELL DISCHARGE ----


- 1. PIPE BEDDING SHALL BE A NATURAL RUN-OF-BANK (R.O.B.) SAND GRADED FROM FINE TO COARSE PARTICLES, OR A GRADED MIXTURE OF CRUSHED STONE OR CRUSHED GRAVEL. BEDDING MATERIAL OR STONE GRADATIONS USED SHALL BE APPROVED BY THE ENGINEER.
- 2. INSTALL CONTINUOUS DETECTABLE MARKING TAPE DURING BACKFILLING OF TRENCH FOR UNDERGROUND WATER SERVICE PIPING. LOCATE TAPE 12" BELOW FINISHED GRADE, DIRECTLY OVER PIPING.
- 3. THE PROPOSED WATERMAINS SHALL BE INSTALLED WITH A MINIMUM COVER OF 4.5 FEET AND SHALL BE CEMENT LINED DUCTILE IRON, CLASS 52.

4. SHEETING SHALL BE IMPLEMENTED IN ACCORDANCE WITH O.S.H.A. STANDARDS.

WATER PIPE TRENCH DETAIL NOT TO SCALE




WET TAP DETAIL



1. NO DEVIATION IN THE SEPARATION REQUIREMENTS WILL BE PERMITTED WITHOUT THE

SANITARY/STORM SEWER-WATER MAIN SEPARATION DETAIL



- 1. SERVICE LINE SHALL HAVE NO JOINTS BETWEEN THE WATER MAIN AND BUILDING
- 2. CORPORATION STOP SHALL BE MANUFACTURED BY MUELLER CO. OR EQUAL.
- 3. BACKFLOW PREVENTION IS NEEDED ON WATER SERVICES CONNECTIONS AND SHOULD BE APPROVED WITH THE ORANG COUNTY DEPARTMENT OF HEALTH AND THE TOWN OF NEWBURGH

WATER DEPARTMENT. WATER SERVICE CONNECTION DETAIL

SCHEDULE OF JOINT RESTRAINT DUCTILE IRON PIPE (DIP) (NO. OF PIPE LENGTHS - 18' LENGTH)							
PIPE SIZE	FITTING						
(INCHES)	90°	45 °	22 1/2°	TEE	INLINE VALVE	DEAD END (SEE NOTE 3)	
12"	2	1	1	4	4	4	
10"	2	1	1	4	4	4	
8"	2	1	1	3	3	3	
6"	1	1	1	2	2	2	

- 1. LENGTH OF PIPE TO BE RESTRAINED IS LENGTH FOR EACH SIDE OF THE FITTING, i.e., FOR A 8" PIPE A 90° BEND SHALL BE RESTRAINED 2 LENGTHS ON EACH SIDE OF THE BEND.
- JOINTS ARE TO BE RESTRAINED TYPE USING RESTRAINED GLANDS OR TIE RODS, IN ACCORDANCE WITH THE LENGTHS SHOWN IN THE TABLE ABOVE.
- 3. DEAD ENDS MUST BE FULLY BACKFILLED BEFORE PRESSURE TESTING AND MUST HAVE BLOCKING (CONCRETE BLOCK) TO UNDISTURBED
- 4. THIS TABLE IS FOR COMPACTED R.O.B. GRAVEL PIPE BEDDING BELOW THE PIPE TO ONE FOOT ABOVE THE PIPE (AWWA TYPE 4

TOWN OF NEWBURGH WATER SYSTEM NOTES

OR 5 LAYING CONDITIONS).

- 1. "CONSTRUCTION OF POTABLE WATER UTILITIES AND CONNECTION TO THE TOWN OF NEWBURGH WATER SYSTEM REQUIRES A PERMIT FROM THE TOWN OF NEWBURGH WATER DEPARTMENT. ALL REQUIREMENTS SHALL CONFORM TO THE REQUIREMENTS OF THE NYSDOH AND THE TOWN OF NEWBURGH".
- 2. ALL WATER SERVICE LINES FOUR (4) INCHES AND LARGER IN DIAMETER SHALL BE CEMENT CLASS 52 DUCTILE IRON PIPE CONFORMING TO ANSI/AWWA C151/A21.51-91 FOR DUCTILE IRON PIPE. JOINTS SHALL BE EITHER PUSH-ON OR
- 3. THRUST RESTRAINT OF THE PIPE SHALL BE THROUGH THE USE OF JOINT RESTRAINT. THRUST BLOCKS ARE NOT ACCEPTABLE. JOINT RESTRAINT SHALL BE THROUGH THE USE OF MECHANICAL JOINT PIPE WITH RETAINER GLANDS. ALL FITTINGS AND VALVES SHALL ALSO BE INSTALLED WITH RETAINER GLANDS FOR JOINT RESTRAINT. RETAINER GLANDS SHALL BE EBBA IRON MEGALUG SERIES 1100 OR APPROVED EQUAL. THE USE OF A MANUFACTURED RESTRAINED JOINT PIPE IS ACCEPTABLE WITH PRIOR APPROVAL OF THE WATER DEPARTMENT.
- 4. ALL FITTINGS SHALL BE CAST IRON OR DUCTILE IRON, MECHANICAL JOINT, CLASS 250 AND CONFORM TO ANSI\AWWA C110\A21.10-87 FOR DUCTILE AND GRAY IRON FITTINGS OR ANSI\AWWA C153\A21.53-94 FOR DUCTILE IRON COMPACT FITTINGS.
- 5. ALL VALVES 4 TO 12 INCHES SHALL BE RESILIENT WEDGE GATE VALVES CONFORMING TO ANI/AWWA C509 SUCH AS MUELLER MODEL A-2360-23 OR APPROVED EQUAL. ALL GATE VALVES SHALL OPEN LEFT (COUNTERCLOCKWISE)
- 6. TAPPING SLEEVES SHALL BE MECHANICAL JOINT SUCH AS MUELLER H-615 OR EQUAL. TAPPING VALVES 4 TO 12 INCHES SHALL BE RESILIENT WEDGE GATE VALVES CONFORMING TO ANSI/AWWA C509 SUCH AS MUELLER MODEL T-2360-19 OR APPROVED EQUAL. ALL TAPPING SLEEVES AND VALVES SHALL BE TESTED TO 150 PSI MINIMUM; TESTING OF THE TAPPING SLEEVE AND VALVE MUST BE WITNESSED AND ACCEPTED BY THE TOWN OF NEWBURGH WATER DEPARTMENT PRIOR TO
- 7. ALL WATER SERVICE LINES TWO (2) INCHES IN DIAMETER AND SMALLER SHALL BE TYPE K COPPER TUBING. CORPORATION STOPS SHALL BE MUELLER H-15020 FOR 3/4 AND 1 INCH, MUELLER H-15000 OR B-25000 FOR 1 1/2 AND 2 INCH SIZES. CURB VALVES SHALL BE MUELLER H-1501-2 FOR 3/4 AND 1 INCH AND MUELLER B-25204 FOR 1 1/2 AND 2 INCH SIZES. CURB BOXES SHALL BE MUELLER H-10312 FOR 3/4 AND 1 INCH AND MUELLER H-10310 FOR 1 1/2 AND 2
- 8. HYDRANTS SHALL BE CLOW-EDDY F 2640 MEETING THE FOLLOWING REQUIREMENTS:
 - A.) ONE 4-1/2 INCH PUMPER NOZZLES; B.) TWO 2-1/2 INCH HOSE NOZZLES;

WATER DEPARTMENT.


- C.) NOZZLE THREADS SHALL BE NST; D.) OPEN LEFT (COUNTER-CLOCKWISE);
- E.) 6 INCH INLET WITH 5-1/4 INCH MAIN VALVE; F.) PAINTED EQUIPMENT YELLOW; AND
- G.) 1-1/2 INCH PENTAGON OPERATING NUTS. 9. ALL PIPE INSTALLATION SHALL BE SUBJECT TO INSPECTION BY THE TOWN OF NEWBURGH WATER DEPARTMENT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING ALL INSPECTIONS AS REQUIRED WITH THE TOWN OF NEWBURGH
- 10. THE WATER MAIN SHALL BE TESTED, DISINFECTED AND FLUSHED IN ACCORDANCE WITH THE TOWN OF NEWBURGH REQUIREMENTS. ALL TESTING, DISINFECTION AND FLUSHING SHALL BE COORDINATED WITH THE TOWN OF NEWBURGH WATER DEPARTMENT. PRIOR TO PUTTING THE WATER MAIN IN SERVICE SATISFACTORY SANITARY RESULTS FROM A CERTIFIED LAB MUST BE SUBMITTED TO THE TOWN OF NEWBURGH WATER DEPARTMENT. THE TEST SAMPLES MUST BE COLLECTED BY A REPRESENTATIVE OF THE TESTING LABORATORY AND WITNESSED BY THE TOWN OF NEWBURGH WATER DEPARTMENT.
- 11. THE FINAL LAYOUT OF PROPOSED WATER AND/OR SEWER CONNECTIONS, INCLUDING ALL MATERIALS, SIZE AND LOCATION OF SERVICE AND ALL APPURTENANCES, IS SUBJECT TO THE REVIEW AND APPROVAL OF THE TOWN OF NEWBURGH WATER AND/OR SEWER DEPARTMENT. NO PERMITS SHALL BE ISSUED FOR A WATER AND/OR SEWER CONNECTION UNTIL A FINAL LAYOUT IS APPROVED BY THE RESPECTIE DEPARTMENT.


V 9 8 4 8 C -

D % ARDNE

SHEET NO. 12 OF 16

DATE: JANUARY 28, 2016





PRECAST MANHOLE DETAILS

DOGHOUSE MANHOLE DETAIL

NOT TO SCALE

SANITARY SEWER NOTES:

MARK WITH A VERTICAL 2"x4" STAKE EXTENDING 2' ABOVE FINISH GRADE

FUTURE CONNECTION

ALTERNATE

CONNECTION (NOT PREFERRED)

PLUG LINE FOR FUTURE CONNECTION

FUTURE CONNECTION

MARK WITH A VERTICAL 2"x4" STAKE EXTENDING

2' ABOVE FINISH GRADE

SERVICE

CONNECTION

→ WATERMAIN


- 1. ALL SANITARY GRAVITY PIPE SHALL BE SDR 35 PVC UNLESS OTHERWISE NOTED, ALL SANITARY SEWER MAINS AND SERVICE LATERALS SHALL BE SEPARATED FROM THE WATER MAINS AND WATER SERVICE CONNECTIONS BY A DISTANCE OF AT LEAST 10 FEET HORIZONTALLY OR 18 INCHES VERTICALLY IF HORIZONTAL SEPARATION IS NOT
- 2. ALL NEW SANITARY SEWER LINES SHALL PASS A LOW PRESSURE AIR TEST AND ALL NEW SANITARY SEWER MANHOLES SHALL PASS HYDROSTATIC TESTS OR VACUUM
- 3. ALL NEW SANITARY SEWER MANHOLE COVERS SHALL BE 24" DIAMETER CAST IRON AND SHALL READ "SANITARY
- 4. ALL SANITARY SEWER CONSTRUCTION SHALL BE SUBJECT TO INSPECTION BY THE MUNICIPAL SEWER SUPERINTENDENT
- PRIOR TO BACKFILLING. 5. THE DESIGN, CONSTRUCTION AND INSTALLATION SHALL BE IN ACCORDANCE WITH THIS PLAN AND GENERALLY ACCEPTED STANDARDS IN EFFECT AT THE TIME OF

CONSTRUCTION WHICH INCLUDE:

- "NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION AND ULSTER COUNTY DEPARTMENT OF
- HEALTH POLICIES, PROCEDURES AND STANDARDS." . "ORANGE COUNTY DEPARTMENT OF HEALTH SANITARY
- "RECOMMENDED STANDARDS FOR WASTEWATER FACILITIES, 2014", GLUMRB.
- "DESIGN STANDARDS FOR WASTEWATER TREATMENT WORKS, 2014", NYSDEC. 6. ALL WELLS AND SUBSURFACE SEWAGE DISPOSAL SYSTEMS
- EXISTING OR APPROVED WITHIN 200' OF THE PROPOSED WATER AND SEWAGE UTILITIES ARE SHOWN ON THIS PLAN ALONG WITH ANY OTHER KNOWN ENVIRONMENTAL HAZARDS IN THE AREA THAT MAY AFFECT THE DESIGN AND FUNCTIONAL ABILITY OF THE WATER AND SEWAGE UTILITIES.
- 7. NO CELLAR, ROOF OR FOOTING DRAINS SHALL BE DISCHARGED INTO THE SEWAGE SYSTEM.

TOWN OF NEWBURGH SANITARY SEWER SYSTEM NOTES

- 1. CONSTRUCTION OF SANITARY SEWER FACILITIES AND CONNECTION TO THE TOWN OF NEWBURGH SANITARY SEWER SYSTEM REQUIRES A PERMIT FROM THE TOWN OF NEWBURGH SEWER DEPARTMENT. ALL CONSTRUCTION SHALL CONFORM TO THE REQUIREMENTS OF THE NYSDEC AND THE TOWN OF NEWBURGH.
- 2. ALL SEWER PIPE INSTALLATION SHALL BE SUBJECT TO INSPECTION BY THE TOWN OF NEWBURGH SEWER DEPARTMENT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING ALL INSPECTIONS AS REQUIRED WITH THE TOWN OF NEWBURGH SEWER DEPARTMENT.
- 3. ALL GRAVITY SANITARY SEWER SERVICE LINES SHALL BE 4 INCHES IN DIAMETER OR LARGER AND SHALL BE SDR-35 PVC PIPE CONFORMING TO ASTM D-3034-89. JOINTS SHALL BE PUSH-ON WITH ELASTOMERIC RING GASKET CONFORMING ASTM D-3212. FITTINGS SHALL BE AS MANUFACTURED BY THE PIPE SUPPLIER OR EQUAL AND SHALL HAVE A BELL AND SPIGOT CONFIGURATION COMPATIBLE WITH THE PIPE.
- 4. THE SEWER MAIN SHALL BE TESTED IN ACCORDANCE WITH TOWN OF NEWBURGH REQUIREMENTS. ALL TESTING SHALL BE COORDINATED WITH THE TOWN OF NEWBURGH SEWER
- 5. THE FINAL LAYOUT OF THE PROPOSED WATER AND/OR SEWER CONNECTION, INCLUDING ALL MATERIALS, SIZE AND LOCATION OF SERVICE AND ALL APPURTENANCES, IS SUBJECT TO THE REVIEW AND APPROVAL OF THE TOWN OF NEWBURGH WATER AND/OR SEWER DEPARTMENT. NO PERMITS SHALL BE ISSUED FOR A WATER AND/OR SEWER CONNECTION UNTIL A FINAL LAYOUT IS APPROVED BY THE RESPECTIVE DEPARTMENT.



NOTE: 1. NO DEVIATION IN THE SEPARATION REQUIREMENTS WILL BE PERMITTED WITHOUT THE EXPRESS APPROVAL OF THE DEPARTMENT OF HEALTH.

SANITARY/STORM SEWER-WATER MAIN SEPARATION DETAIL


NOT TO SCALE

10/20/23 7/6/23 9/6/22 6/6/22 6/21/17 5/30/17 3/15/16 V 0 0 4 E 2 -


RIDGI WN ROA NE ERT SANITAR GARD GARDNE


13 OF 16


DATE: JANUARY 28, 2016 FILE NO.



14 OF 16 DATE: JANUARY 28, 2016








HAY BALE CHECK DAM

NOT TO SCALE




CONSTRUCTION SPECIFICATIONS 1. BALES SHALL BE PLACED IN A ROW WITH ENDS TIGHTLY ABUTTING THE


- 2. EACH BALE SHALL BE EMBEDDED IN THE SOIL A MINIMUM OF 4". 3. BALES SHALL BE SECURELY ANCHORED IN PLACE BY STAKES OR RE-BARS DRIVEN THROUGH THE BALES. THE FIRST STAKE IN EACH BALE SHALL BE ANGLED TOWARD PREVIOUSLY LAID BALE TO FORCE BALES
- 4. INSPECTION SHALL BE FREQUENT AND REPAIR OR REPLACEMENT SHALL BE MADE PROMPTLY AS NEEDED.
- 5. BALES SHALL BE REMOVED WHEN THEY HAVE SERVED THEIR USEFUL-NESS SO AS NOT TO BLOCK OR IMPEDE STORM FLOW OR DRAINAGE.
- 6. HAYBALES SHALL BE PLACED IN ACCORDANCE WITH THE NEW YORK STATE GUIDELINES FOR URBAN EROSION AND SEDIMENT CONTROL.


HAY BALE DETAILS

NOT TO SCALE



NOT TO SCALE





GENERAL CONSTRUCTION NOTES:

PLAN WRITTEN FOR THIS PROJECT.

STABILIZED.

REACHED.

1. ALL CONTRACTORS SHALL COMPLY WITH THE STORMWATER POLLUTION PREVENTION

PRIOR TO THE START OF WORK. THE CONTRACTOR SHALL BE FAMILIAR WITH THE

INTENT OF THIS PLAN AND ENSURE THAT WORK TO BE PERFORM IS THE SAME.

APPROVALS, ETC. FOR WORK PERFORMED FROM AGENCIES HAVING JURISDICTION

NOTIFY THE ENGINEER. SHOULD HE FAIL TO FOLLOW THIS PROCEDURE AND CONTINUE

4. IF IN THE COURSE OF CONSTRUCTION A CONDITION EXISTS WHICH DISAGREES WITH THAT AS INDICATED ON THESE PLANS, THE CONTRACTOR SHALL STOP WORK AND

WITH THE WORK, HE SHALL ASSUME ALL RESPONSIBILITY AND LIABILITY ARISING

5. COMPACTION OF ALL FILL MATERIAL SECTIONS SHALL BE COMPLETED IN 6" LIFTS.

6. MAINTAIN POSITIVE EROSION CONTROL DURING THE OPERATION UNTIL THE SITE IS

8. THE ENTIRE SITE IS TO BE STABILIZED WITH VEGETATION WHEN FINAL GRADES ARE

9. TEMPORARY SEED MIX SHALL BE PERENNIAL RYEGRASS @ 30 POUNDS/ACRE OR AS RECOMMENDED BY THE SULLIVAN COUNTY SOIL CONSERVATION DISTRICT.

LBS/ACRE, TALL FESCUE 20 LBS/ACRE, PERENNIAL RYEGRASS 5 LBS/ACRE OR AS

SEEDING MAY BE PERFORMED AT OTHER TIMES PER YEAR IF PROPERLY MULCHED AND

ADEQUATE MOISTURE PROVIDED. SEEDING IN AREAS THAT FAIL MUST BE RESEEDED

KNOWN TO HAVE PERCHED WATER TABLES. UPON ENCOUNTERING GROUNDWATER THE

AND SLOPE STABILITY IMPACTS BY ANY OF THE APPLICABLE METHODS DISCUSSED IN

THE STORMWATER POLLUTION PREVENTION PLAN FOR THIS PROJECT OR SCHEDULING

CONSTRUCTION IN THESE AREAS SO AS TO AVOID THEM DURING WET PERIODS OF THE

10. PERMANENT SEED MIX SHALL BE THE FOLLOWING: COMMON WHITE CLOVER 8

RECOMMENDED BY THE SULLIVAN COUNTY SOIL CONSERVATION DISTRICT.

DURING THE FOLLOWING OPTIMUM TIME FOR SEEDING.

CONTRACTOR MAY MITIGATE EROSION

11. THE OPTIMUM TIME FOR SEEDING IS EARLY SPRING AND LATE AUGUST. HOWEVER

12. CONTRACTORS SHALL NOTE THAT SOME OF THE SOILS LOCATED ON THE SITE ARE


7. THE CONTRACTOR SHALL PROVIDE ADDITIONAL TOPSOIL FOR RECLAMATION PROCEDURES


EACH LIFT SHALL BE COMPACTED TO 95% OF THE PROCTOR DENSITY.

3. CONTRACTOR SHALL OBTAIN ALL REQUIRED APPROVALS, PERMITS, INSPECTION

2. CONTRACTOR SHALL CHECK AND VERIFY ALL CONDITIONS AT THE SITE


HAY BALE INSTALLATION AT CATCH BASINS






SEDIMENT CONTROL STRUCTURES

AT CENTER -FILTER FABRIC






CONSTRUCTION SPECIFICATIONS:

1. STONE WILL BE PLACED ON A FILTER FABRIC FOUNDATION. 2. SET SPACING OF CHECK DAMS TO ESTABLISH THE ELEVATIONS OF THE CREST OF THE DOWNSTREAM DAM AT THE SAME ELEVATION OF THE TOE OF THE UPSTREAM DAM.

SECTION A-A

- 3. EXTEND THE STONE A MINIMUM OF 1.5 FEET BEYOND THE DITCH BANKS TO PREVENT CUTTING AROUND THE DAM. 4. PROTECT THE CHANNEL DOWNSTREAM OF THE LOWEST CHECK DAM FROM SCOUR AND EROSION WITH STONE OR LINER AS APPROPRIATE. 5. ENSURE THAT CHANNEL APPURTENANCES SUCH AS CULVERT ENTRANCES BELOW CHECK DAMS ARE NOT SUBJECT TO DAMAGE OR BLOCKAGE FROM DISPLACED STONES.
- 6. USE GRADED STONE 2 TO 15 INCHES IN SIZE (NYS-DOT LIGHT STONE FILL MEETSTHESE REQUIREMENTS).

CHECK DAM DETAILS




CONSTRUCTION ENTRANCE NOTES

1. SURFACE SHALL BE 2" CRUSHED STONE OR RECLAIMED/RECYCLED CONCRETE.

- 2. THE MINIMUM LENGTH SHALL BE 50 FEET (30' FOR A SINGLE RESIDENCE LOT).
- 3. THE TRACKING PAD SHALL BE A MINIMUM OF 6" DEEP STONE. 4. THE MINIMUM WIDTH SHALL BE 12 FEET.
- 5. A FILTER FABRIC SHALL BE PLACED UNDER THE ENTRANCE PRIOR TO PLACEMENT OF THE STONE (CONTECH C-40NW OR EQUAL).
- 6. SURFACE WATER SHALL BE DIVERTED AWAY FROM THE CONSTRUCTION ENTRANCE THROUGH THE USE OF DIVERSION SWALES AND PIPING. IF PIPING IS IS NOT FEASIBLE, THEN A MOUNTABLE BERM WITH 5:1 SLOPES SHALL BE USED.
- 7. THE STABILIZED CONSTRUCTION ENTRANCE SURFACE SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OR FLOW OF MUD OR SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY. PERIODIC TOP DRESSING WITH ADDITIONAL STONE WILL BE NEEDED AS CONDITIONS DEMAND. REPAIR AND CLEAN ALL MEASURES USED TO TRAP SEDIMENT ANY SEDIMENT THAT IS TRANSPORTED ON TO THE PUBLIC RIGHT OF WAY (IN ANY MANNER) MUST BE REMOVED

STABILIZED CONSTRUCTION ENTRANCE

NOT TO SCALE



1. FILTER FABRIC SHALL HAVE AN EOS OF 40-85.

2. WOODEN FRAME SHALL BE CONSTRUCTED OF 2" x 4" CONSTRUCTION GRADE LUMBER.

3. WIRE MESH ACROSS THROAT SHALL BE A CONTINUOUS PIECE 30 INCH MINIMUM WIDTH WITH A LENGTH 4 FEET LONGER THAN THE THROAT. IT


SHALL BE SHAPED AND SECURELY NAILED TO A 2" x 4" WEIR. 4. THE WEIR SHALL BE SECURELY NAILED TO 2" x 4" SPACERS 9 INCHES LONG SPACED NO MORE THAN 6 FEET APART. 5. THE ASSEMBLY SHALL BE PLACED AGAINST THE INLET AND SECURED BY

2" x 4" ANCHORS 2 FEET LONG EXTENDING ACROSS THE TOP OF THE INLET

AND HELD IN PLACE BY SANDBAGS OR ALTERNATE WEIGHTS. 6. MAXIMUM DRAINAGE AREA 1 ACRE

CURB DROP INLET PROTECTION

NOT TO SCALE



EROSION & SEDIMENT CONTROL MEASURES

1. TEMPORARY DIVERSION SWALES TEMPORARY DIVERSION SWALES WILL BE INSTALLED IMMEDIATELY UPHILL OF AREAS SCHEDULED TO BE DISTURBED FOR THE PURPOSE OF DIVERTING STORMWATER. SWALES SHALL BE MAINTAINED UNTIL THE REGRADED SITE IS STABILIZED WITH PERMANENT SEEDING.

2. STABILIZED CONSTRUCTION ENTRANCE TEMPORARY GRAVEL CONSTRUCTION ENTRANCE(S) SHALL BE INSTALLED IMMEDIATELY ADJACENT TO THE EXISTING PAVEMENT. DURING WET WEATHER IT MAY NECESSARY TO WASH VEHICLE TIRES AT THIS LOCATION. THE ENTRANCE SHALL BE GRADED OFF SO THAT RUNOFF WILL BE DIRECTED TO AN EXISTING CATCH BASIN AND AWAY FROM THE PAVEMENT. ALL SEDIMENT SHALL BE PREVENTED FROM ENTERING CATCH BASINS.

SILT FENCES SHALL BE INSTALLED IN THE LOCATIONS SPECIFIED ABOVE, AROUND TOPSOIL STOCKPILE AREAS. AT THE BASE OF ALL DISTURBED SLOPES, AND AT INTERVALS NECESSARY TO PREVENT CONCENTRATION OF FLOW.

4. <u>VEGETATION PROTECTION</u>

LIMIT SOIL PLACEMENT OVER EXISTING TREES AND SHRUB ROOTS TO A MAXIMUM OF 3 INCHES. USE SOILS WITH LOAMY TEXTURES AND GOOD STRUCTURE. CONSTRUCT STURDY FENCES, WOOD OR STEEL BARRIERS, OR OTHER PROTECTIVE DEVICES TO SURROUND AND PROTECT SENSITIVE OR VALUABLE VEGETATION FROM CONSTRUCTION EQUIPMENT. PLACE BARRIERS FAR ENOUGH FROM TREES SO THAT TALL EQUIPMENT SUCH AS BACKHOES AND DUMP TRUCKS DO NOT DAMAGE TREE BRANCHES.

CONSTRUCTION LIMITS SHOULD BE IDENTIFIED AND CLEARLY MARKED TO EXCLUDE EQUIPMENT. IT IS STRONGLY RECOMMENDED THAT CONSTRUCTION FENCING BE UTILIZED TO PROTECT AREAS THAT ARE NOT TO BE DISTURBED. OBSTRUCTIVE AND BROKEN BRANCHES SHOULD BE PRUNED PROPERLY. EXISTING VEGETATION SHOULD BE PRESERVED WHERE ATTAINABLE.

5. LAND GRADING FINISH LAND SURFACES WILL BE GRADED AS INDICATED ON THE PLANS. AT A MAXIMUM, NO MORE THAN 5 ACRES OF UNPROTECTED SOIL SHOULD BE EXPOSED AT ANY ONE TIME.

AREAS TO BE FILLED SHALL BE CLEARED, GRUBBED, AND STRIPPED OF TOPSOIL. REMOVE TREES, VEGETATION, ROOTS, OR OTHER UNACCEPTABLE MATERIAL. FILL MATERIAL SHALL BE FREE OF BRUSH, RUBBISH, LOGS, STUMPS, BUILDING DEBRIS, AND OTHER ORGANIC MATERIAL. FROZEN MATERIAL SHALL NOT BE PLACED IN THE FILL NOR SHALL THE FILL MATERIAL BE PLACED ON A FROZEN FOUNDATION.

UNLESS OTHERWISE NOTED, PROVIDE TEMPORARY VEGETATION BY SEEDING BARE SOIL WITHIN 7 DAYS OF EXPOSURE UNLESS CONSTRUCTION WILL BEGIN WITHIN 14 DAYS. IF CONSTRUCTION IS SUSPENDED, ALL AREAS SHALL BE SEEDED AND MULCHED IMMEDIATELY.

FINISH GRADING SHALL BE COMPLETED SO AS TO PREVENT WATER FROM STANDING ON THE SURFACE OF LAWNS FOR MORE THAN 24 HOURS AFTER THE END OF A RAINFALL. TOPSOIL REQUIRED FOR THE ESTABLISHMENT OF VEGETATION WILL BE STOCKPILED IN THE AMOUNT NECESSARY TO COMPLETE FINISHED GRADING OF ALL EXPOSED, NON-SODDED AREAS. STOCKPILES SHALL BE SEEDED IN ACCORDANCE WITH THESE PLANS.

AREAS THAT ARE TO BE TOPSOILED SHALL BE SCARIFIED TO A MINIMUM DEPTH OF THREE INCHES PRIOR TO PLACEMENT OF TOPSOIL.

6. <u>DUST CONTROL</u> 15 MPH CONSTRUCTION ZONE SPEED LIMIT SIGNS SHALL BE ERECTED IN ALL AREAS WHERE

DUSTLESS SURFACES HAVE NOT BEEN CONSTRUCTED.

CONSTRUCTION OPERATIONS SHALL BE SCHEDULED TO MINIMIZE THE AMOUNT OF AREA DISTURBED AT ONE TIME. BUFFER AREAS OF VEGETATION SHALL BE LEFT WHERE POSSIBLE. THE SITE, INCLUDING HAUL ROADS AND ACCESS ROADS, CAN BE SPRINKLED WITH WATER UNTIL THE SURFACE IS WET. THE FOLLOWING SPRAY ADHESIVES CAN BE USED ON MINERAL

MATERIAL	WATER DILUTION	TYPE OF NOZZLE	
ACRYLIC POLYMER	9:1	COARSE SPRAY	
LATEX EMULSION	12.5:1	FINE SPRAY	
RESIN IN WATER	4:1	FINE SPRAY	

7. TEMPORARY AND PERMANENT SEEDING SEEDING PREPARATION INCLUDES REMOVAL OF DEBRIS, ROCKS, STUMPS AND OTHER UNACCEPTABLE MATERIALS. COMPACTED SOIL SHALL BE SCARIFIED PRIOR TO PLACEMENT OF TOPSOIL. ADJUST PH TO 6.0 WITH LIME AND FERTILIZE WITH 600 LBS OF 5-10-10 OR EQUIVALENT PER ACRE. ALL DISTURBED AREAS SHALL BE TEMPORARILY SEEDED IF CONSTRUCTION DOES NOT RESUME IN 7 DAYS. AND BEFORE ANY SIGNIFICANT STORM EVENT WHICH MAY HAVE THE POTENTIAL TO CAUSE EROSION.

ALL APPROVED STOCKPILES AND OTHER DISTURBED OR GRADED AREAS SHALL BE SEEDED WITHIN 14 CALENDAR DAYS PROVIDED CONSTRUCTION GRADING ACTIVITY IS NOT CONTINUALLY ONGOING IN THESE LOCATIONS.

APPLY TEMPORARY SEEDING CONSISTING OF QUICK GERMINATING RYEGRASS (ANNUAL OR

PERENNIAL) AT 30 LBS. PER. ACRE. PERMANENT SEEDING SHALL BE COMPLETED WITHIN 7 DAYS OF COMPLETION OF FINAL GRADING. SEED MIXTURE SHALL BE APPLIED IN ACCORDANCE WITH THESE PLANS AND/OR

THE RECOMMENDATIONS OF THE LOCAL SOIL & WATER CONSERVATION DISTRICT.

THE OPTIMUM TIME FOR PERMANENT SEEDING IS IN THE SPRING FROM MARCH 21 THROUGH MAY 20, AND IN LATE SUMMER AND EARLY FALL FROM AUGUST 25 TO OCTOBER 15. PERMANENT SEEDINGS MAY BE MADE ANY TIME OF YEAR IF PROPERLY MULCHED AND ADEQUATE MOISTURE IS PROVIDED. BROADCASTING, DRILLING WITH CULTIPACK TYPE SEEDER OR HYDROSEEDING ARE ACCEPTABLE. COLD WEATHER SEEDING SHALL BE PERFORMED USING WINTER GERMINATING SEED SUCH AS WINTER RYE.

8. TOPSOIL/MULCHING WHERE VEGETATION WILL BE ESTABLISHED, PRESERVE AND APPLY EXISTING TOPSOIL AND FRIABLE FINE TEXTURED SUBSOILS THAT ARE STRIPPED DURING EXCAVATION. COMPLETE ROUGH GRADING AND FINAL GRADING, ALLOWING FOR DEPTH OF TOPSOIL TO BE ADDED. SCARIFY ALL COMPACT, SLOW PERMEABLE, MEDIUM, AND FINE TEXTURED SUBSOIL AREAS. IN SOIL AREAS THAT ARE STEEPER THAN 5 PERCENT, SCARIFY AT APPROXIMATELY RIGHT ANGLES TO THE SLOPE. REMOVE REFUSE, WOODY PLANT PARTS, STONES OVER 3 INCHES IN DIAMETER AND OTHER LITTER.

TOPSOIL SHALL HAVE A MINIMUM OF 2 PERCENT AND A MAXIMUM OF 6 PERCENT (BY WEIGHT) OF FINE TEXTURED STABLE ORGANIC MATERIAL. TOPSOIL SHALL HAVE NOT LESS THAN 20 PERCENT FINE TEXTURED MATERIAL (PASSING THE NO. 200 SIEVE) AND NOT MORE THAN 15 PERCENT CLAY. TOPSOIL SHALL BE RELATIVELY FREE OF STONES OVER 1 1/2 INCHES IN DIAMETER.

TOPSOIL SHALL BE PLACED AT A UNIFORM DEPTH OF 4 INCHES FOR THE STEEP SLOPES, 6 INCHES FOR THE LAWN AREAS AND 2" FOR UNMOWED GRASS AREAS. TOPSOIL SHALL NOT BE PLACED WHEN IT IS PARTLY FROZEN, MUDDY, NOR ON FROZEN SLOPES OR OVER ICE, SNOW OR STANDING WATER. TOPSOIL PLACED AND GRADED ON SLOPES STEEPER THAN 5 PERCENT SHALL BE PROMPTLY FERTILIZED, SEEDED, MULCHED AND STABILIZED BY "TRACKING" WITH SUITABLE EQUIPMENT.

IF SOIL IS COMPACTED OR CRUSTED, SURFACE SHOULD BE LOOSENED TO AT LEAST TWO INCHES BY DISKING OR OTHER SUITABLE METHODS.

9. INSPECTION OF EROSION AND SEDIMENT CONTROL MEASURES THE OWNER OR QUALIFIED REPRESENTATIVE OF THE OWNER SHALL INSPECT THE EROSION AND SEDIMENT CONTROL MEASURES AT LEAST ONCE EVERY 7 CALENDAR DAYS AT A MINIMUM, THESE MEASURES INCLUDE THE DISTURBED AREAS OF THE CONSTRUCTION SITE, THE AREAS USED FOR STORAGE OF MATERIALS THAT ARE EXPOSED TO STRUCTURAL CONTROL MEASURES AND THE LOCATIONS WHERE VEHICLES ENTER AND EXIT THE SITE. WHERE PORTIONS OF THE CONSTRUCTION AREA HAVE BEEN FINALLY STABILIZED, INSPECTION

THE TERM "FINALLY STABILIZED" MEANS THAT ALL THE SOIL DISTURBING ACTIVITIES AT THE SITE HAVE BEEN COMPLETED AND THAT A UNIFORM PERENNIAL VEGETATIVE COVER WITH A DENSITY OF 70 % FOR THE AREA HAS BEEN ESTABLISHED OR EQUIVALENT STABILIZATION

OF SUCH PORTIONS SHALL BE CONDUCTED AT LEAST ONCE EVERY MONTH UNTIL THE ENTIRE

MEASURES (SUCH AS THE USE OF MULCHES OR GEOTEXTILES) HAVE BEEN EMPLOYED. 10. MAINTENANCE REQUIREMENTS AND SCHEDULES EROSION AND SEDIMENT CONTROL MEASURES ALL EROSION AND SEDIMENT CONTROL

SITE IS FINALLY STABILIZED.

MEASURES SHALL BE INSPECTED FOR STABILITY AND OPERATION FOLLOWING EVERY RUNOFF PRODUCING RAINFALL BUT IN NO CASE LESS THAN ONCE EVERY WEEK. ANY NEEDED REPAIRS SHALL BE MADE IMMEDIATELY TO MAINTAIN ALL MEASURES AS DESIGNED.

SEDIMENT SHALL BE REMOVED FROM BEHIND THE SILT FENCE WHEN IT BECOMES APPROXIMATELY 6 INCHES DEEP AT THE FENCE. ENSURE THAT NO CONCENTRATED FLOWS ARE DIRECTED TOWARDS THE FENCE. REPLACE THE SILT FENCE WHEN "BULGES" DEVELOP IN THE FENCE.

ALL SEEDED AREAS SHALL BE FERTILIZED. RE-SEEDED AS NECESSARY AND MULCHED TO MAINTAIN A VIGOROUS, DENSE VEGETATIVE COVER.


SEDIMENT SPILLED, DROPPED OR WASHED ONTO EXISTING MACADAM ROADWAYS MUST BE MOVED IMMEDIATELY. ALL SEDIMENT SHALL BE PREVENTED FROM ENTERING THE STORM DRAINS. ADDITIONAL AGGREGATE SHALL BE ADDED TO THE STABILIZED CONSTRUCTION ENTRANCES AS REQUIRED.


MAINTAIN DUST CONTROL MEASURES THROUGH DRY WEATHER PERIODS UNTIL ALL DISTURBED AREAS ARE STABILIZED.


15 OF 16


/20/23 /6/23 /6/22 /6/22 /21/17 /30/17


DATE: JANUARY 28, 2016























GARDNER RIDGE ASSOCIATES, LLC

ORANGE COUNTY