

TOWN OF NEWBURGH PLANNING BOARD TECHNICAL REVIEW COMMENTS

PROJECT NAME:NEWBURGH CHICKEN, LLC - POPEYESPROJECT NO.:23-17PROJECT LOCATION:197 SOUTH PLANK ROAD/SECTION 60, BLOCK 3, LOT 6.1REVIEW DATE:11 DECEMBER 2024MEETING DATE:19 DECEMBER 2024PROJECT REPRESENTATIVE:DYNAMIC ENGINEERING

- 1. The project is before the Board for a Public Hearing. Any substantive comments received should be addressed by the applicant's representative.
- 2. County Planning comments dated 17 January2024 have been received. County Planning comments issued a local determination with advisory comments.
- 3. The projects site is a 0.97 +/- acre parcel of property. The land disturbance will be slightly larger than that. Project results in potentially greater than 1 acre disturbance. A SWPPP has been prepared for the project. Under parking infiltration system has been designed for the redevelopment site. A proprietary stormwater practice is being utilized for pretreatment of the water quality.
- 4. The stormwater management system has resulted in a reduction in run off for all storm events. The project will require a permit from NYSDEC for a stormwater discharge.
- 5. Infiltration rates for the soils under the basin should be provided. Infiltration testing in accordance with NYSDEC permits should be incorporated into the plan. Ground water separation must be documented.
- 6. A Stormwater Facilities Maintenance Agreement will be required for the project.
- 7. Security for stormwater management and landscaping is required. Cost estimates should be prepared and submitted for review. Town Board approval of the cost estimates and inspection escrow is required.
- 8. NYSDOT has issued a conceptual sign off letter dated 25 November 2024. Highway work permit should be obtained prior to issuance of building permit.
- 9. The project is a Type II Action under SEQRA.
- 10. A design for the retaining wall must be submitted for a building permit after site plan approval.

NEW YORK OFFICE

PENNSYLVANIA OFFICE

- 11. A minimum number of trees are proposed to be removed from the redevelopment site. Tree removal plan has been added to Sheet 3 of 20 of the plan set.
- 12. The water supply line for potable water and sprinkler water has been redesigned in compliance with Town requirements.
- 13. The project is subject to ARB approval. Planning Board should review building architecture and signage.
- 14. A typo on the outlet control structure at the 2-foot weir identifies an invert at 561.5 based on the stormwater model it should be 361.5.
- 15. Details should depict the valve on the 4-inch drain for the underground storage at invert 358.
- 16. 36" HDPE pipes should be identified as perforated in the details.

Respectfully submitted,

MHE Engineering, D.P.C.

when of Alene

Patrick J. Hines Principal PJH/kmm

I W Went

Michael W. Weeks, P.E. Principal

Link to Download Site Plans:

https://mhepc.egnyte.com/dl/ZzRoCRPuTn